


CRITICAL SHIFT

REACTOR / CENTERED EAST CONTROL ROOM

A100

GENERAL ARRANGEMENT



EQUIPMENT / RETAINED GAMEPLAY SECTORS

ID	STATION	FOOTPRINT / m
01	FUEL RECEIVING	2.40 x 2.40
02	NEW FUEL RACK	2.40 x 1.80
03	BANK / REACTIVITY	1.80 x 1.80
04	WASTE TRANSFER	2.40 x 2.40
05	CONTAINMENT VENT	1.20 x 1.20
06	TURBINE / THROTTLE	2.10 x 4.20
07	GRID BREAKERS	1.20 x 3.00
08	GRID DEMAND	1.80 x 1.20
09	CONTAINMENT SENSOR	0.48 x 0.48
10	COOLANT PUMP	2.40 x 2.40
11	COOLANT VALVES	2.40 x 1.80
12	EMERGENCY COOLING	3.00 x 2.40
13	BACKUP GENERATOR	2.40 x 2.40
14	RESERVE POWER	1.50 x 3.00
15	REPAIR / SPARES	1.80 x 1.80

LAYOUT INTENT

- 01 Four short flights stack in one 20.00 m2 core.
- 02 Control and window align with the reactor axis.
- 03 Top landing opens into the Control room.
- 04 North-hinged D01 clears the vestibule approach.
- 05 Two banks and the pool retain their spec scale.
- 06 North workstations flank a clear entry apron.

CIRCULATION / KEY

Pool service ring: 1 300 radial width.
Maintain at least 1 200 usable circulation.
* Turbine-to-ring minimum: 1 312 measured.
South rail gate: 1 400 clear; approach: 1 800.
Grey dashed: upper Control room outline.
Amber: compact stair / access route.
Cyan: pool, glazing and observation zones.

COORDINATES / SOURCE

Plan north is up. Dimensions are millimetres.
Hall datum 0.000; Control datum +10.000.
Current reactor scenery spec governs the envelope.
This is a new 2D proposal; no old 3D assets used.
Style direction retained: brighter second concept.

SCHEMATIC DESIGN / GAME ENVIRONMENT

Dimensions: mm | Levels: m relative to hall FFL 0.000

A2 / 594 x 420 mm / print at 100% for stated scales

DRAWING

GENERAL ARRANGEMENT

SCALE

1:100

REV P02

07 SEP 2026

01 / 05

CRITICAL SHIFT


REACTOR / CENTERED EAST CONTROL ROOM

A101

CONTROL + STACKED STAIR PLANS

02 / CONTROL FLOOR +10.000

P02: room and glazing centerline is exactly $Y = 0.000$



V01 / WINDOW + VIEW STRIP

5 400 x 2 600 main pane
650 interior glazed floor strip
See V01 detail on A202.

Y = 0 / HALL + REACTOR AXIS

ROOM USE

- Two seated operator positions.
- Clear 1 300 walk-up zone.
- Desks face the hall glazing.
- Plant mimic on rear wall.
- No separate gallery corridor.

STACKING LOGIC

F1 east / F2 west / F3 east / F4 west.

Plan cut: 1 200 above each tagged level; cut flight shown broken.


Dashed stair is above cut; tinted slab is the current landing.

Top exit returns to the west landing at +10.000.

56 risers total; no exposed hall stair or overlook.

Landing doors swing out of the stair clear rectangles.


03 / LEVEL +0.000



F1: 14R @ 178.571 / 13G @ 250

UP TO +2.500 / D01 ENTRY


04 / LEVEL +2.500



F2: 14R @ 178.571 / 13G @ 250

UP TO +5.000 / DN TO +0.000


05 / LEVEL +5.000



F3: 14R @ 178.571 / 13G @ 250

UP TO +7.500 / DN TO +2.500

06 / LEVEL +7.500



F4: 14R @ 178.571 / 13G @ 250

UP TO +10.000 / DN TO +5.000

SCHEMATIC DESIGN / GAME ENVIRONMENT

Dimensions: mm | Levels: m relative to hall FFL 0.000

A2 / 594 x 420 mm / print at 100% for stated scales

DRAWING

CONTROL + STACKED STAIR PLANS

SCALE

1:50

REV P02

07 SEP 2026

02 / 05


CRITICAL SHIFT

REACTOR / CENTERED EAST CONTROL ROOM

A201

SECTIONS + SIGHTLINES


A-A / REACTOR + CONTROL



SCHEMATIC SIGHTLINES / PLAN OCCLUSION NOT TESTED

Targets: far floor / pool water / near-wall work zone. Glazing detail V01 on A202.

B-B / LONGITUDINAL STAIR SECTION



Nosing pitch: 35.54 deg
Same-band flights repeat at 5.00 m vertical separation.

SCHEMATIC DESIGN / GAME ENVIRONMENT

Dimensions: mm | Levels: m relative to hall FFL 0.000

A2 / 594 x 420 mm / print at 100% for stated scales

DRAWING

SECTIONS + SIGHTLINES

SCALE

1:100 / 1:50

REV P02


07 SEP 2026

03 / 05


E01 / EAST WALL - VIEWED FROM HALL




C-C / WEST LANDING + CONTROL DOOR



D01 / ENTRY SECTION



V01 / OBSERVATION SECTION - 1:10



SCHEMATIC DESIGN / GAME ENVIRONMENT

Dimensions: mm | Levels: m relative to hall FFL 0.000

A2 / 594 x 420 mm / print at 100% for stated scales

DRAWING

ENTRANCE + OBSERVATION DETAILS

SCALE

1:50 / 1:10

REV P02

07 SEP 2026

04 / 05


CRITICAL SHIFT

REACTOR / CENTERED EAST CONTROL ROOM



A301

STAIR DETAIL + SCHEDULES

07 / ENCLOSED STAIR - ENLARGED



08 / HANDRAIL CLEARANCE - 1:20



STAIR SCHEDULE

Core gross: 6 250 x 3 200 = 20.00 m2.
Flight band: 1 300 gross / 1 200 rail-clear.
Central well: 200 between flight edges.
End landings: 1 300 gross / 1 250 clear.
Outer enclosure: 200 nominal.
Per flight: 14 risers / 13 goings.
Riser: 10 000 / 56 = 178.571 mm.
Going: 250 mm; nosing pitch: 35.54 deg.
2R + G = 607.143 mm.
Lowest landing underside: +2.300.
Main floor to Control: +10.000 exactly.

LEVEL / FLIGHT SCHEDULE

F1 0.000 to +2.500 / eastbound.
F2 +2.500 to +5.000 / westbound.
F3 +5.000 to +7.500 / eastbound.
F4 +7.500 to +10.000 / westbound.
Historic +4.8 overlook is removed.

OPENINGS / ROOM SCHEDULE

D01 Stair entry: 1 200 clear x 2 100 high.
D02 Control entry: 1 200 clear x 2 100 high.
W01 Main observation: 5 400 x 2 600.
V01 Interior glazed strip: 650 + 280 reveal.
Control clear: 3 600 x 6 400 = 23.04 m2.
Vestibule clear: 1 300 x 4 000 = 5.20 m2.
East hall route remains 4 000 x 5 000.

COORDINATION NOTES

D01 north-hinged into vestibule; D02 into Control.
Flight guards stay inside the tread bands.
Gross dimensions are nominal exact-fit chains.
Room and window are centered on east-wall Y=0.
Print A2 at 100%; use dimensions, not screen size.

SCHEMATIC DESIGN / GAME ENVIRONMENT

Dimensions: mm | Levels: m relative to hall FFL 0.000

A2 / 594 x 420 mm / print at 100% for stated scales

DRAWING

STAIR DETAIL + SCHEDULES

SCALE

1:25 / 1:20 / 1:5

REV P02

07 SEP 2026

05 / 05